

Section	Violation Description Shown on Driver/Vehicle Examination Report Given to CMV Driver after Roadside Inspection	Violation Group Description	Violation Severity Weight ¹⁹	Violation in the DSMS (Y/N)
393.100(b)	Leaking/spilling/blowing/falling cargo	Improper Load Securement	7	Y
393.100(c)	Failure to prevent cargo shifting	General Securement	1	Y
393.102(a)	Improper securement system (tiedown assemblies)	Tiedown	3	Y
393.102(a)(1)	Insufficient means to prevent forward movement	Failure to Prevent Movement	3	Y
393.102(a)(1)(i)	Insufficient means to prevent forward movement	Failure to Prevent Movement	3	Y
393.102(a)(1)(ii)	Insufficient means to prevent rearward movement	Failure to Prevent Movement	3	Y
393.102(a)(1)(ii i)	Insufficient means to prevent lateral movement	Failure to Prevent Movement	3	Y
393.102(a)(2)	Tiedown assembly with inadequate working load limit	Tiedown	3	Y
393.102(b)	Insufficient means to prevent vertical movement	Failure to Prevent Movement	3	Y
393.102(c)	No equivalent means of securement	Improper Load Securement	7	Y
393.104(a)	Inadequate/damaged securement device/system	Securement Device	1	Y
393.104(b)	Damaged securement system/tiedowns	Securement Device	1	Y
393.104(c)	Damaged vehicle structures/anchor points	Securement Device	1	Y
393.104(d)	Damaged dunnage/bars/blocking-bracing	Securement Device	1	Y
393.104(f)(1)	Knotted tiedown	Tiedown	3	Y
393.104(f)(2)	Use of tiedown with improper repair.	Tiedown	3	Y
393.104(f)(3)	Loose/unfastened tiedown.	Tiedown	3	Y
393.104F4R	No edge protection for tiedowns	Tiedown	3	Y
393.106(a)	No/improper front end structure/headerboard	Securement Device	1	Y

Section	Violation Description Shown on Driver/Vehicle Examination Report Given to CMV Driver after Roadside Inspection	Violation Group Description	Violation Severity Weight ¹⁹	Violation in the DSMS (Y/N)
393.106(b)	Cargo not immobilized or secured	Failure to Prevent Movement	3	Y
393.106(c)(1)	No means to prevent cargo from rolling	Failure to Prevent Movement	3	Y
393.106(c)(2)	Cargo without direct contact/prevention from shifting	Failure to Prevent Movement	3	Y
393.106(d)	Insufficient aggregate working load limit	Tiedown	3	Y
393.110	Failing to meet minimum tiedown requirements	General Securement	1	Y
393.110(b)	Insufficient tiedowns; without headerboard/blocking	Tiedown	3	Y
393.110(c)	Insufficient tiedowns; with headerboard/blocking	Tiedown	3	Y
393.110(d)	Large/odd-shaped cargo not adequately secured	Failure to Prevent Movement	3	Y
393.112	Tiedown not adjustable by driver	Securement Device	1	Y
393.114	No/improper front end structure	General Securement	1	Y
393.114(b)(1)	Insufficient height for front-end structure	Securement Device	1	Y
393.114(b)(2)	Insufficient width for front-end structure	Securement Device	1	Y
393.114(d)	Front-end structure with large opening(s)	Securement Device	1	Y
393.116	No/improper securement of logs	General Securement	1	Y
393.116(d)(1)	Short, over 1/3 length past structure	Improper Load Securement	7	Y
393.116(d)(2)	Short, insufficient/no tiedowns	Improper Load Securement	7	Y
393.116(d)(3)	Short, tiedowns improperly positioned	Improper Load Securement	7	Y
393.116(d)(4)	Short, no center stakes/high log not secured	Improper Load Securement	7	Y

Section	Violation Description Shown on Driver/Vehicle Examination Report Given to CMV Driver after Roadside Inspection	Violation Group Description	Violation Severity Weight¹⁹	Violation in the DSMS (Y/N)
393.116(e)	Short, length; improper securement	Improper Load Securement	7	Y
393.118	No/improper lumber/building materials. securement	General Securement	1	Y
393.118(b)	Improper placement of bundles	Improper Load Securement	7	Y
393.118(d)	Insufficient protection against lateral movement	Failure to Prevent Movement	3	Y
393.118(d)(3)	Insufficient/improper arrangement of tiedowns	Tiedown	3	Y
393.120	No/improper securement of metal coils	General Securement	1	Y
393.120(b)(1)	Coil/vertical improper securement	Improper Load Securement	7	Y
393.120(b)(2)	Coils, rows, eyes vertical - improper securement	Improper Load Securement	7	Y
393.120(c)(1)	Coil/eye crosswise improper securement	Improper Load Securement	7	Y
393.120(c)(2)	X-pattern on coil(s) with eyes crosswise	Improper Load Securement	7	Y
393.120(d)(1)	Coil with eye lengthwise-improper securement	Improper Load Securement	7	Y
393.120(d)(4)	Coils, rows, eyes length - improper securement.	Improper Load Securement	7	Y
393.120(e)	No protection against shifting/tipping	Failure to Prevent Movement	3	Y
393.122	No/improper securement of paper rolls	General Securement	1	Y
393.122(b)	Rolls vertical - improper securement	Improper Load Securement	7	Y
393.122(c)	Rolls vertical /split - improper securement	Improper Load Securement	7	Y
393.122(d)	Rolls vertical /stacked - improper securement	Improper Load Securement	7	Y

Section	Violation Description Shown on Driver/Vehicle Examination Report Given to CMV Driver after Roadside Inspection	Violation Group Description	Violation Severity Weight ¹⁹	Violation in the DSMS (Y/N)
393.122(e)	Rolls crosswise - improper securement	Improper Load Securement	7	Y
393.122(f)	Rolls crosswise/stacked load - improperly secured	Improper Load Securement	7	Y
393.122(g)	Rolls length - improper securement	Improper Load Securement	7	Y
393.122(h)	Rolls lengthwise/stacked - improper securement	Improper Load Securement	7	Y
393.122(i)	Improper securement - rolls on flatbed/curtain-sided vehicle	Improper Load Securement	7	Y
393.124	No/improper securement of concrete pipe	General Securement	1	Y
393.124(b)	Insufficient working load limit - concrete pipes	Tiedown	3	Y
393.124(c)	Improper blocking of concrete pipe	Improper Load Securement	7	Y
393.124(d)	Improper arrangement of concrete pipe	Improper Load Securement	7	Y
393.124(e)	Improper securement, up to 45 in. diameter	Improper Load Securement	7	Y
393.124(f)	Improper securement, greater than 45 inch diameter	Improper Load Securement	7	Y
393.126	Fail to ensure intermodal container secured	General Securement	1	Y
393.126(b)	Damaged/missing tiedown/securement device	Securement Device	1	Y
393.126(c)(1)	Lower corners of container not on vehicle/structure	Securement Device	1	Y
393.126(c)(2)	All corners of chassis not secured	Improper Load Securement	7	Y
393.126(c)(3)	Front and rear of container not secured independently	Improper Load Securement	7	Y
393.126(d)(1)	Empty container not properly positioned	Improper Load Securement	7	Y

Section	Violation Description Shown on Driver/Vehicle Examination Report Given to CMV Driver after Roadside Inspection	Violation Group Description	Violation Severity Weight¹⁹	Violation in the DSMS (Y/N)
393.126(d)(2)	Empty container, more than 5 foot overhang	Improper Load Securement	7	Y
393.126(d)(4)	Empty container - not properly secured	Improper Load Securement	7	Y
393.128	No/improper securement of vehicles	General Securement	1	Y
393.128(b)(1)	Vehicle not secured - front and rear	Improper Load Securement	7	Y
393.128(b)(2)	Tiedown(s) not affixed to mounting points.	Improper Load Securement	7	Y
393.128(b)(3)	Tiedown(s) not over/around wheels.	Improper Load Securement	7	Y
393.130	No/improper heavy vehicle/machinery securement	General Securement	1	Y
393.130(b)	Item not properly prepared for transport	Improper Load Securement	7	Y
393.130(c)	Improper restraint/securement of item	Improper Load Securement	7	Y
393.132	No/improper securement of crushed vehicles	General Securement	1	Y
393.132(b)	Prohibited use of synthetic webbing.	Securement Device	1	Y
393.132(c)	Insufficient tiedowns per stack cars	Tiedown	3	Y
393.132(c)(5)	Insufficient means to retain loose parts	Improper Load Securement	7	Y
393.134	No/improper securement of roll/hook container	General Securement	1	Y
393.134(b)(1)	No blocking against forward movement	Failure to Prevent Movement	3	Y
393.134(b)(2)	Container not secured to front of vehicle	Improper Load Securement	7	Y
393.134(b)(3)	Rear of container not properly secured	Improper Load Securement	7	Y
393.136	No/improper securement of large boulders	General Securement	1	Y

Section	Violation Description Shown on Driver/Vehicle Examination Report Given to CMV Driver after Roadside Inspection	Violation Group Description	Violation Severity Weight¹⁹	Violation in the DSMS (Y/N)
393.136(b)	Improper placement/positioning of boulder	Improper Load Securement	7	Y
393.136(c)(1)	Boulder not secured with chain	Improper Load Securement	7	Y
393.136(d)	Improper securement - cubic boulder	Improper Load Securement	7	Y
393.136(e)	Improper securement - non-cubic boulder with stable base	Improper Load Securement	7	Y
393.136(f)	Improper securement - non-cubic boulder with unstable base	Improper Load Securement	7	Y